TABLE OF CONTENTS

1.0	Certification [40 CFR 112.3(d)]	1
2.0	Review [40 CFR 112.5]	2
3.0	Management Approval [40 CFR 112.3(d)]	3
4.0	Facility Owner and Operator Information	4
5.0	Personnel Responsibilities and Organization	5
6.0	Purpose of the Plan	6
7.0	Facility and Vicinity Information	7
7.1	Facility Description	7
7.2	Facility Drainage	7
7.3	Storage Areas and Capacity	8
7.4	Process Areas	9
7.5	Loading and Unloading Areas	10
7.6	Sewer System	10
7.7	Vicinity Description	10
8.0	Spill History [40 CFR 112.7(a)]	10
9.0	Potential Releases [40 CFR 112.7(b) and (c)(1)]	11
10.0	Impracticability of Containment/Diversionary Structures and Equipment [40 CFR 112.7(d)]	13

11.0 Release Prevention and Containment Procedures 13

11.1 Drainage Control [40 CFR 112.7(c) and 112.8 (b)] 13
11.1.1 Drainage Control In Bermed Storage Areas 14
11.1.2 Plant Drainage Systems for Unbermed Areas 14
11.1.3 Final Drainage Discharge 15
11.1.4 Drainage Systems 15

11.2 Bulk Storage Containers [40 CFR 112.8 (c)] 15
11.2.1 Tank Compatibility 15
11.2.2 Secondary Containment 15
11.2.3 Rainwater Drainage 16
11.2.4 Corrosion Protection of Buried Metallic Storage Tanks 16
11.2.5 Corrosion Protection of Partially Buried Metallic Storage Tanks 17
11.2.6 Aboveground Tank Periodic Integrity Tests 17
11.2.7 Control of Leakage Through Internal Heating Coils 18
11.2.8 Tank Installation Fail-safe Engineering 18
11.2.9 Plant Effluent Discharges 18
11.2.10 Visible Oil Leaks 19
11.2.11 Mobile or Portable Oil Storage Containers 19

11.3 Facility Transfer Operations [40 CFR 112.8 (d)] 19
11.3.1 Buried Piping Installation Protection and Examination 19
11.3.2 Out-of-Service and Standby Service Pipes 19
11.3.3 Piping Support Design 20
11.3.4 Aboveground Valve and Pipeline Examination 20
11.3.5 Aboveground Piping Protection from Vehicle Traffic 20

11.4 Facility Tank Car and Truck Loading and Unloading Operations [40 CFR 112.8(h)] 20
11.4.1 Department of Transportation Regulations 21
11.4.2 Secondary Containment for Vehicles 21
11.4.3 Warning or Barrier System for Vehicles 21
11.4.4 Lowermost Drainage Outlet Examination 21

Appendices

A	Inspection Guidelines and Checklist
B	Training Records
C	Loading/Unloading Procedures
D	Oil Spill Emergency Response Plan
E	Certification That This Facility Does Not Pose Substantial Harm
F	Replacement Schedule

SPILL PREVENTION

2.0 Review [40 CFR 112.5]

This plan will be reviewed and evaluated at least once every five years and within six months of a change in facility design, construction, operation, or maintenance that materially affects TU's spill potential. In response to the reviews, the SPCC plan will be amended within six months of the review date to include more effective prevention and control technology, if that technology has been proven in the field and will significantly reduce the likelihood of a spill. Amendments to this SPCC plan will be reviewed and certified by a Registered Professional Engineer per 40 CFR 112.3(d) and 112.5(c).

Review Date	**Signature**

Amendment Date	**Sections Amended**	**Signature**

4.0 Facility Owner and Operator Information

Facility Name	Towson University
Facility Type	University Campus
Facility Location and Mailing Address	8000 York Road Towson, Maryland 21252
Hours of Normal Operation	24 Hours/day 7 Days/week
Facility Phone Number	
Working Hours	(410) 704-3806/2488
After Hours	(410) 704-4444 (24-hours)

TU Poli1 72EMC /P /MC1 0 0 1 144.02 501.31 Tm[( )] TJET)

5.0 Personnel Responsibilities and Organization

The personnel responsible for implementing this SPCC plan are listed below. These persons are thoroughly familiar with the SPCC regulations and this SPCC plan and have overall responsibility for implementing this SPCC plan. They will maintain the records required under this SPCC plan and a copy of the complete current SPCC plan, as amended, for on-site review by EPA during normal working hours, as required by 40 CFR 112.3(e).

Mr. Larry Holbrook, Director of Environmental Health and Safety
(410) 704-3806 (Office)
(443) 603-4118 (cell)

Mr. Rick Walsh, Associate Director-Operations and Maintenance
(410) 704-2488 (Office)
(410) 808-5236

7.3 Storage Areas and Capacity

The campus contains two heating oil USTs, and four (4) oil-water separator UST. The subject site has various ASTs for storing fuel for emergency generators, heating oil, kerosene, vehicle fuel storage tanks, waste oil tanks, grease tanks, and oil-filled electrical transformers. Table 1, in section 9.0, lists the tanks on campus.

The subject site also contains a hazardous waste storage area, vehicle maintenance bays, and a vehicle fueling station. In addition, there are several small, miscellaneous oil storage containers across the facility. No portable oil storage areas or wastewater treatment plants are on campus.

The locations of TU's ASTs are described below:

> Emergency generator tanks are located at various buildings on campus. Most of the emergency generator ASTs are approximately 150-gallon, single-walled "belly" tanks. Table 1, in section 9.0, lists the tanks on campus.
>
> Electrical oil-filled transformers are located across the TU campus. Most of the electrical transformers are approximately 300-gallon, single-walled tanks with heat sink fins. Two larger electrical oil-filled transformers are located in a gravel filled area near the Power Plant.
>
> TU also has a 150-gallon double-walled waste oil AST and two (2) 275-gallon double- walled motor oil AST at the General Services Facility. Also stored at the General Services Facility are a portable generator with a 175 gallon diesel belly tank, and a 500 gallon portable skid-type AST for diesel or heating oil. Both of these portable units have secondary containment tanks.
>
> TU has a 240-gallon day tank, and a 3,000 gallon double-walled fuel tank AST at the Hawkins Hall/Psychology for an emergency generator that services the Educational complex. (Installed in 2010)
>
> TU has one 1,000-gallon, double-walled, double internal compartment AST at

Two, 30,000-

Spill response equipment is staged at the Power Plant, which is centrally located on campus; the General Services Facility, EHS's Equipment Storage Building, Facilities Management Vehicles (Director & Associate Director), EHS's Truck, as well as other locations on campus. In addition, an enclosed trailer with spill equipment plus additional resources supplies are stored in the General Services Truck Well.

In addition, TU has a local outside oil response contractor (Triumvirate Environmental of Baltimore, Maryland) available to assist in the employing controls and countermeasures and spill response and cleanup. The contractor is available 24 hours a day (800) 966-9282 and will deploy a response team immediately upon authorization by TU. The recovered oil will be properly disposed of or treated by Triumvirate.

10.0 Impracticability of Containment/Diversionary Structures and Equipment [40 CFR 112.7(d) and (e)]

Due to the potential electrical hazard that may be created by the installation of containment dikes around the electrical transformers and switches, TU will maintain a thorough periodic inspection program for electrical equipment with oil storage.

TU has implemented a testing program using ultrasonic pulse-echo equipment to check the thickness of the metal walls of the outdoor ASTs that are considered bulk storage tanks (excludes the electrical switches and transformers). The test results are included in Appendix G. Two walls of each tank were tested. See Section 11.2.6 for additional information on the testing program. The tests will be performed as directed by the University's consultant. ASTs whose wall thickness is considered a substantial risk will be eventually replaced.

11.0 Release Prevention and Containment Procedures

11.1 Drainage Control [40 CFR 112.7(c) and 112.8 (b)]

Drainage control at TU is not specifically designed to contain spills. If a spill were to reach the storm drain, it would be routed to one of the streams that cross the campus.

TU will replace all oil filled electrical transformers and switches at the end of their service life. Transformers will be replaced with either a dry type or oil filled. The determination of which type (dry or oil) will be based on numerous factors such as efficiency, operating costs, service life, energy savings, safety, vandalism, etc. Oil switches will be replaced with dry types. Service life will be determined by an outside electrical testing contractor on an annual basis. In cases where transformers are leaking, they will be repaired, if feasible. Leaking oil switches will be replaced with dry types.

11.1.1 Drainage Control In Bermed Storage Areas

There are two bermed electrical transformers at TU: Glen Complex Dining Hall, and the Media Center. The two bermed storage areas require additional work to effectively contain leaks. None of the storage areas are covered.

Valves are not currently used on TU's bermed storage areas—all areas are closed, without drains, except for the Power Plant. Portable pumps will be used to empty bermed areas, after inspection to ensure that oil-

11.1.3 Final Drainage Discharge

The streams that cross the TU campus discharge to Towson Run Branch, which is tributary of Lake Roland.

11.1.4 Drainage Systems

TU does not have a drainage system or a water treatment unit. If a drainage system is installed in the future, the system will be designed to prevent oil from reaching a waterway in the event of equipment failure or human error.

11.2 Bulk Storage Containers [40 CFR 112.8 (c)]

11.2.10 Visible Oil Leaks

Facility personnel are trained to visually inspect tank seams, gaskets, rivets, bolts, flanges, and joints for visible oil leaks. Oil leaks and/or spills are to be reported immediately to EHS and corrected as soon as possible. EHS personnel will evaluate the situation to determine what response and reporting is required (see Appendix D for Oil Spill Emergency Response Plan).

11.2.11 Mobile or Portable Oil Storage Containers [40 CFR 112.8(c)(11)]

TU does not currently have any mobile or portable oil storage tanks. If such tanks are employed at TU in the future, secondary containment will be provided. They will not be located in areas of periodic flooding or washout.

11.3 Facility Transfer Operations [40 CFR 112.8(d)]

11.3.1 Buried Piping Instal

11.3.3 Piping Support Design

11.4.1 Department of Transportation Regulations

TU will require that the oil delivery companies drivers sent to TU are trained and will comply with Department of Transportation (DOT) regulations (49 CFR 177) and facility standard operating procedures for loading and unloading operations. The truck drivers will be instructed by their own dispatchers to make no deliveries or pick-ups unless a TU representative is present to authorize, direct, and oversee loading and unloading operations.

11.4.2 Secondary Containment for Vehicles

There are currently no catch basins, treatment systems, or secondary containment systems for loading/unloading operations at TU.

TU will install curbing systems and/or seal down gradient storm-water drains while trucks load oil

11.5 Oil Production Facilities (Onshore) [40 CFR 112.9]

TU is not an oil production facility and therefore this section of the SPCC regulations is not applicable to TU.

11.6 Oil Drilling and Work Over Facilities (Onshore) [40 CFR 112.10]

TU is not an oil drilling and work over facility and therefore this section of the SPCC regulations is not applicable to TU.

11.7 Oil Drilling, Production, or Work Over Facilities (Offshore) [40 CFR 112.11]

TU is not an oil drilling and work over facility and therefore this section of the SPCC regulations is not applicable to TU.

11.8 Inspections, Tests, and Records [40 CFR 112.7(c) and 112.8 (c)]

Facility personnel will be trained to be observant during normal operations for signs of malfunctions or problems that might lead to leaks, spills, or other releases.

Monthly visual inspections will be conducted for oil storage tanks, piping, pumps, and drum storage areas to identify leaks, seepage, stained soils, or signs of significant deterioration. Identifiable accumulations of oil will be cleaned-up promptly and the cause of the accumulation will be determined and repaired. Abnormal tank conditions and repairs made will be reported to Mr. Hughes. Any leaks, spill response or breach in tank integrity will be recorded in the tank inspection checklist located in Appendix A.

TU will be responsible for ensuring that the required inspections, training, and tests are conducted; signing the reports of those activities; and keeping the reports and associated records for at least three years.

11.9 Security [112.7(g)]

TU is an unsecured facility with minimal fencing or other barriers to public access. TU will ensure that pipeline connections are securely capped and locked when not in use. Drains and valves will be locked in the closed position.

11.10 Personnel Training [112.7(f)]

TU will conduct annual training sessions to instruct staff in proper housekeeping; operation and maintenance of equipment; laws and regulations; spill prevention, detection, and response activities; and notification requirements. A more detailed outline of the training program is provided below.

a. Personnel responsible for duties set forth under the SPCC plan are thoroughly familiar with the plan and its requirements.

b. Personnel who may become directly involved with a release will be trained, including oil-handling personnel. The training will address regulations, known spill events and failures, loading/unloading operations, malfunctioning components, and precautionary measures. Training sessions may include timed practice placement of control and countermeasure devices and materials and other simulations of spills.

c. Training sessions will be conducted at intervals frequent enough so that an adequate understanding of the SPCC plan is achieved. A record of attendance will be kept. At a minimum, training sessions will be held annually.

d. Employees who may become directly involved in a spill will be trained on how to prevent spills according to this SPCC plan and good management practices.

e. None of the employees are to be designated “first responders” for incidents

hazardous materials unit of the local fire department for stabilization of the situation and then to the spill response contractor for cleanup.

12.0 Facility Response Plans [40 CFR 112.20]

ALWE concluded that TU is not a substantial harm facility as defined in 40 CFR 112.20(f) and therefore not required to prepare and submit a Facility Response Plan (FRP). Appendix E contains the Certification That This Facility Does Not Pose Substantial Harm as required by Section 3 of Appendix C to 40 CFR 112. This has been signed and certified by a representative of TU.

13.0 Facility Response Training and Drills/Exercises [40 CFR 112.20]

Since the facility is not a substantial harm facility (Section 12), this section is not applicable to TU.

APPENDIX A

INSPECTION GUIDELINES AND CHECKLIST

APPENDIX B

TRAINING RECORDS

APPENDIX C

LOADING/UNLOADING PROCEDURES

Loading and Unloading Procedures

Purpose: to provide for oil transfers from tank trucks to the on

APPENDIX D

OIL SPILL EMERGENCY RESPONSE PLAN

(d) Proceed to source of spill, spread absorbent material, and collect oil saturated absorbent in 55-gallon leak proof 55 drums.

(e) Flush storm drain with water and repeat steps (a) 2 and (c) above. Continue this process until all oil has been retrieved.

(f) The ranking Facilities Management Manager/EHS Representative at the scene will make a visual inspection of Towson Run and areas affected by oil spill to ascertain that in fact all oil has been recovered.

(g) If the size of the oil spill exceeds the capability of TU personnel to handle, the following outside contractor should be contacted by the ranking Facilities Management Manager/EHS Representative present:

Triumvirate Environmental

Baltimore, Maryland 21226

Telephone: 800-966-9282

(h) Contact authorized waste oil disposal company to dispose of 55-gallon drums containing oil saturated absorbent material.

4. The following is available for spill control at the General Service Facility:

(a) Shovels, rakes, etc., from Grounds and Transportation Departments.

(b) Back hoe and pay loader from Grounds and Transportation Departments.

(c) 40 - 8-inch x 18-inch absorbent pillows

(d) 22 - 8-inch x 18-foot absorbent booms

(e) 10 - fabric socks

(f) 4 - 4-foot x 200-foot absorbent rolls (1 medium and 3 heavy duty)

(g) 2 - 20-gallon lockable spill waste containers

(h) 1- Spill Blocker (rough surface)

(i) 1- PIG Conical Drain Plug Kit

(j) 2 - Round Drain Blockers

(k) 1 - PIG Drain Blocker Plug (48 in.)

(l) 2 - PIG Oil Only Spill Pads (16 ½ in. x 20 in.) 200/bag

(m) 4 – PIG Spill Kits (1 each in Assoc. Director/Trades Mgr. Vehicles). Each kit contains 3-3 in. x 48 in. PIG socks, 12-16 ½ in. x 20 in. PIG mats-double pads and disposal bags.

NOTE: additional resources/supplies will be maintained at the Power Plant

APPENDIX E

CERTIFICATION OF APPLICABILITY OF THE SUBSTANTIAL HARM CRITERIA

_____ yes ___X___ no

CERTIFICATION:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document, and that based on my inquiry of those individuals responsible for obtaining this information, I believe that the submitted information is true, accurate, and complete.

_____	_____
Signature	Signature
Lawrence A. Holbrook	Rick Walsh
Name	Name
Director of Environmental Health and Safety	Associate Director-Operations & Maintenance
Title	Title
_____	_____
Date	Date

APPENDIX F

REPLACEMENT SCHEDULE

APPENDIX G

AST WALL THICKNESS TEST RESULTS

APPENDIX H

CROSS REFERENCE TO REGULATIONS

FIGURES